
## TEKRAM TECHNOLOGY CO., LTD. DC-680, DC-680T



USER CONFIGURABLE SETTINGS		
Function	Location	Setting
í IDE-0 damping resistor enabled	JDR0	open
IDE-0 damping resistor disabled	JDR0	closed
í IDE-1 damping resistor enabled	JDR1	open
IDE-1 damping resistor disabled	JDR1	closed

Continued on next page . . .

Copyright © 1991, 1992, 1993 by Micro House Int'I (800) 926-8299. Research Dept. (303) 443-3389

## TEKRAM TECHNOLOGY CO., LTD. DC-680, DC-680T

... continued from previous page

DRIVE ACTIVE LED ERROR CODES (IMMEDIATELY AFTER POWE ₹-UP)		
Status	Function	
One short flash	No cache DRAM installed	
Two short flashes	CPU error	
Three short flashes	SRAM error	
Four short flashes	Timer error	

## MISCELLANEOUS TECHNICAL NOTES Some versions of this board have two 512KB x 8 DRAM chips mounted in place of Bank 0. In such a case the board will work without additional memory. In all other cases a pair of 256KB, 1MB, or 4MB SIMM modules must be installed in Bank 0 for the board to function. Jumpers JP3 and JP4 are factory-configured - do not alter.

Copyright @ 1991, 1992, 1993 by Micro House Int'l (800) 926-8299. BBS (303) 443-9957